

Residential Dwelling Units - Prescribed Inspection List

- The inspections listed below are mandatory when applicable to your project.
- You are required to notify the Building Division when your project is ready for each inspection: 519-941-2816 ext. 2700 or building@dufferincounty.ca
- Inspections will take place next business day if requested by 3:00pm.

Building Inspections:

| Type of Inspection | When to Call for Inspection |
|-------------------------------|--|
| Footings | At completion of formwork, before pouring concrete on undisturbed soil free of standing water, mud, and loose earth |
| Foundation (Backfill) | Ready for backfilling of foundation, damp proofing applied, weeping tile covered with stone (min. 6 inches of cover) |
| Framing | At completion including rough-in of plumbing and HVAC |
| Insulation and Vapour Barrier | At completion of insulation and vapour barrier, before installing interior wallboard |
| Fireplaces and Chimneys | At commencement of installation |
| Occupancy | Review occupancy inspection checklist |
| Final | At completion of interior and exterior construction including final grading |



Plumbing Inspections:

| Type of Inspection | When to Call for Inspection |
|--|--|
| Site Servicing | At completion, before back filling, ready for testing |
| Interior Drains/Underground Plumbing | At completion, before back filling, ready for testing |
| Rough-in Water Supply, Drains, Waste, Vents | At completion, ready for testing |
| Occupancy | At completion of installation of all required fixtures |
| Final | At completion of installation of fixtures |

Mechanical Inspections:

| Type of Inspection | When to Call for Inspection |
|-------------------------------|--|
| Rough-in HVAC, Air Extraction | At completion of rough-in, before installation of insulation |
| Occupancy | Mechanical systems ready for testing |
| Final | Completion of all mechanical systems |

Note: Construction may be done in phases. Such projects may require additional inspections.